

Product details:

Item No.: 844552

Model No.: AJ220

Technical data:

Input:5V/0.8A

Luminous flux of night light: <60Lm

Power of light: around 1W

Tools list:




- 1: Screwdriver
- 2: Utility knife
- 3: Electric screwdriver
- 4: Soldering iron

Instructions on how to remove the light source:

Step1: Remove the screws from the metal cage with screwdriver.




Step2: Pull out the lampshade by hand, exposing the lighting board.




Step3: Remove screws with electric screwdriver and open plastic cover.




Step4: Remove the wire of lighting board by hand and then remove the battery cable by soldering iron.



Step5: Remove the screws on the plastic cover of the lighting board with electric screwdriver to separate the plastic cover from lighting board.



Step6: Use utility knife to raise the wire casing and now the light source was removed without being permanently damaged for verification purposes.



Red line: Positive pole “ + ”

Orange line: Negative pole “-”(cold light)

Yellow line: Negative pole “-”(warm light)